

Generating Energy Through Co-Digestion



City of Fort Worth Village Creek Water Reclamation Facility

Ana J. Pena-Tijerina, Ph.D., P.E., BCEE
VCWRF Technical Services

April 25, 2014

Metropolitan Water Reclamation District of Greater Chicago

Outline

- VCWRF Description
- Journey to Achieve Energy Independence
 - Gas Turbines
 - JCI Energy Performance Contract
- Co-Digestion Phases
 - Planning
 - Implementation
 - Operation
- Lessons Learned

Water Reclamation Facility Treatment, Recovery and Reuse

Service to over 1 million
customers in 23 communities



Trinity River



Reuse Water



Biosolids



Energy

Wastewater



Village Creek WRF



**CITY OF FORT WORTH
VILLAGE CREEK WATER
RECLAMATION FACILITY**

PERMIT = 166 MGD ADF,
7 BOD, 15 TSS, 2/4 NH₃-N

FILTERS

CHLORINE CONTACT


**AERATION BASINS
& FINAL
CLARIFIERS**

FILTERS


THICKENERS

**PRIMARY
CLARIFIERS**


DIGESTERS



Journey to Achieve Energy Independence




Electrical Utilization



Energy Production...

Starts at the 14
Anaerobic Digesters



Operational Parameters


PARAMETER	RANGE OR TARGET
pH Range	6.8 – 7.4
Temperature	95° – 99°
Detention Time	≥15 Days
Volatile Acids	<500 mg/L
Alkalinity	~3000 mg/L
Feed Total Solids %	>2.5%
% Volatile Solids Destruction	≥38%

Operational Challenges



No efficient mixing with gas compression

Operational Challenges



Grit accumulation & loss of treatment volume

Energy Conservation & Recovery

Achieved with the JCI Energy Savings Performance Contract which goals were:


- To improve energy efficiency and enhance energy reduction
- Total project cost of \$36,756,399
- Guarantees an annual O&M and electrical savings of \$3,184,757
- 12 year payback
- No rate impact

JCI Energy Savings Performance Contract Projects


Facility Improvement Measures (FIMs):

1. Diffuser Replacement
2. Heat Recovery Steam Generation
3. Digester Mixing & Co-Generation Facility
4. SCADA replacement
5. Anoxic zones
6. HVAC, Power Factor Correction, pump efficiency

Estimated Electrical Savings



Energy Recovery & Production Schematic



Planning Phase

1. Why consider it?
2. Type of substrate
3. Screening sources
4. Financial and contract considerations



Leveraging The Opportunity

Numerous industries in or near Fort Worth with High Strength Wastes (HSW)



- Batter dumps & DAF float from food processors
- Expired / damaged product from soft drink bottler
- Glycerin and organic acids from biodiesel facility

City's Objective

- City's main objective was to assure reliable, long-term, low-risk supply of HSW to increase biogas production.
- Potential HSW suppliers identified through pretreatment program
 - Contacted with waste characterization surveys
 - Evaluated/accepted on a case by case basis

HSW Hauler's Requirements

- COD > 50,000 mg/L, prefer > 100,000 mg/L
- Pumpable at ambient temperature
- Minimal suspended solids, especially inert solids
- High volatile solids
- No pH adjustment necessary
- No pollutants that threaten digester performance or sludge quality (i.e. heavy metals, sanitizers, sulfates)



HSW Contracting Process

- Conducted by Pre-treatment Services
- Solicit interest from interested parties
- Receive/evaluate potential waste streams
- Procure agreements
 - Accountability, key contact info
 - Contract period
 - Fees
 - Indemnification/liability
 - Delivery mechanisms and time frames (customers arrange for delivery – at their expense – and at prescribed schedule)

Implementation Phase

1. HSW fed to six digesters
2. Improvements to mixing systems
3. Design considerations
4. Design build type project


Based on Dr. Leonard Ripley's Slides



Why Implement Co-Digestion?

1 MG sludge digester:


- 200 lb VSS/kft³-day,
- 75% VSS destruction,
- 10 ft³ CH₄ /lb ΔVSS,
- Methane yield =
 - 8,360 SCF/hr
- Energy yield =
 - 8.0 MM BTU/hr




1 MG co-digestion:

- 2.0 kg COD/m³-day,
- 90% COD destruction
- 6.3 ft³ CH₄ /lb ΔCOD,
- CH₄ yield =
 - 3,940 SCF/hr
- Energy yield =
 - 3.8 MM BTU/hr

Energy Recovery & Production Chart



Feed Distribution Options




Send all HSW to the
sludge blend tank

Feed digesters in a "pod"
to limit pipe length

Feed codigesters through
a new HSW header

Feed Selected Option




Digester Modifications

Mixing: Linear Motion Mixers



Feed: PVC header and valves, open to pulse-feed cycles



Receiving Station

- Dedicated truck ramp, with containment curbs, drain, and wash-down sump
- 30,000-gal mix tank, with chopper pumps, jet mixing and heat exchanger



Metering System


- Two 6,000-gal batch tanks, each with recirculation mixer, and heat exchanger
- PLC to feed operator-specified volume to digesters in pulses.



Mix tank on right, two batch tanks on left

Operational Phase

1. Receiving station
2. Scheduling deliveries
3. Monitor gas production
4. Monitor performance



Receiving HSW


- Clear through security
- Installation of cameras and good lighting
- Operator/supplier offload to complete manifests
- Offloading takes approximately 30 minutes
- Limited storage (ensure tank capacity to offload)



Scheduling Deliveries

- Started slowly in Sept 2012, with filtrate from Liquid Environmental System's grease processing facility
- Gradually added other wastes:
 - South Waste
 - Delek biodiesel
 - Coca-Cola
- Others pending


Gradually Increase of Deliveries






Monitor Performance


- Set feed-rate to match expected deliveries (for consistent, effective gas production)
- Sufficient waste to get through the night/weekend
- Monitor (feed rates, waste characteristics, temperature, digester performance, etc.)






Courtesy of Dr. Leonard Ripley

Overall Gas Utilization



Mass Balance



Performance Monitoring

DIG#	TEMP.	TS%	TS %VOL	PH	TOT.ALK.	VOL. ACID	VA/ALK ratio		TSS(MG/L)	%Vol.
1	96	2.60	58.04	7.09	3125	887	0.28	BLEND TANK	34525	64.2
2	93	2.36	57.84	7.10	2950	717	0.24	DS1 (1-6)	22425	55.3
3	97	2.46	56.05	7.14	3125	687	0.22	DS2 (7-10)	26625	56.3
4	96	2.28	56.69	7.24	3000	729	0.24	DS3 (11-14)		
5	98	2.69	55.58	7.11	2950	620	0.21	DS4 (ALL)	22800	53.7
6	95	2.42	55.01	7.14	3100	711	0.23			
7	95	2.33	55.26	7.24	3150	848	0.27			
8	97	2.59	57.10	7.21	3175	790	0.25			
9	98	2.34	57.48	7.23	3300	826	0.25			
10	97	2.34	56.41	7.21	3350	665	0.20			
11	97	2.56	54.49	7.28	3425	975	0.28			
12	99	2.78	54.41	7.23	3375	814	0.24			
13	99	3.05	57.34	7.25	3600	845	0.23			
14	98	3.05	55.91	7.29	3500	668	0.19			

Lessons Learned


1. Planning is critical
2. Efficient mixing system
3. Balancing sink/sources



Lessons Learned

- HSW planning is critical ... know what you're getting. Village Creek has chosen to be very "picky" about its suppliers to reduce risk of upsets
- Efficient mixing is critical for Co-Digestion
- Balancing financial drivers:
 - Steady, reliable biogas production
 - Divert organic loading from liquid treatment
 - Tipping fee revenue

Challenges



- Equalizing HSW loading from weekdays to weekends
- High temperature of HSW from grease processors greater than 130⁰F
- Odors from truck unloading
- Balancing heat sink/sources

VCWRF Flying Towards Energy Neutrality... The Sky's the Limit

