


NEBRASKA INNOVATION CAMPUS

C.R.E.S.





Seacrest & Kalkowski, PC, LLO

Presentation Outline


- I. General Overview
- II. CRES Financial Operations
- III. Methods of Collecting Revenue
- IV. Preliminary Design
- V. Final Design
- VI. Project Delivery and Construction


Theresa Street Wastewater Treatment Facility

- Nitrification Capacity 27.4 MGD
- Hydraulic Capacity 91MGD
- Nitrification, De-Nitrification
Fine Bubble Aeration
- Vortec Grit Removal
- Anaerobic Sludge Digestion
- Methane Fueled Electrical
Generation (900 kW)
- UV Disinfection
- Enhanced SCADA/Process
Automation
- Chemical Wet Scrubber Odor
Control




General Overview





© Alfa Laval



-  CRES Supply Line
-  CRES Return Line
-  Reclaimed Supply Line
-  Buildings to receive CRES infrastructure (approx. 1.1M sq. ft.)
-  Pump & Heat Exchanger Building
-  Building Service Location
-  Control Building
-  Buildings to receive CRES Phase II infrastructure (approx. 375K sq. ft.)

Phase II
sq. ft.)



- CRES Supply Line
- CRES Return Line
- Reclaimed Supply Line
- Buildings to receive CRES infrastructure (approx. 1.1M sq. ft.)
- Pump & Heat Exchanger Building
- Building Service Location
- Control Building
- Buildings to receive CRES Phase II infrastructure (approx. 375K sq. ft.)

General Overview

1. This system will have the capacity to heat and cool:
 - 1,875,000 SF of lab/office space
 - 1,500 houses at 2,000 SF each
2. 18,000 GPM is equivalent to 7,500 Tons of cooling at a 10 degree delta T.
3. The C.R.E.S. essentially works like a geothermal system but rather than pumping from water from the ground, the water is pumped from the City of Lincoln wastewater plant.
4. Water temperatures range from 57 to 75°F. At these temperatures, buildings will be able to utilize geothermal heat pumps that can operate up to 30% more efficient than standard equipment.

General Overview

Comparison vs. Traditional Systems

System	End User Cost ⁽¹⁾	Efficiency ⁽²⁾	Cooling savings ⁽³⁾	Heating Savings ⁽⁴⁾	Lifespan ⁽⁵⁾
Chillers & Boilers (base system)	100	92%	0%	0%	30 years
Steam & Storage (East Campus)	100	90%	10%	20%	30 years
CRES	100	95%	25%	30%	50 years

(1) Capital cost to install mechanical systems to use source of energy

(2) Annual Fuel Utilization Efficiency (AFUE)

(3) Cooling months energy savings

(4) Heating months energy savings over traditional systems

(5) Project lifespan of mechanical systems

Calculations/Assumptions:

1. Base system uses an air-cooled chiller that meets ASHRAE minimum standards of 2.8 COP.
2. CRES system utilizes a water to water heat pump system that meets ASHRAE minimum standards of 4.2 COP. In this system, the electrical pumping energy is included from the CRES.
3. This savings is only based on summer cooling, as the system will use more electrical energy over the entire year. The reason for this is due to the base system utilizing gas for heating and the CRES using water to water heat pumps. It is important to understand the peak that sets demand will be less in summer and therefore will save demand charges throughout the year.
4. This evaluation considers making the same amount of chilled water throughout the year in both the base and the CRES.
5. **Savings could even be larger as this evaluation does not consider additional free cooling available from the CRES.**

General Overview

C.R.E.S. Bottom Line

1. **More efficient** than geothermal system due to consistent water temperatures and no issues from raising ground temperatures over time
2. System **can easily and economically add on new users** up to the 28 million gallons per day capacity
3. **Renewable and sustainable source of energy** with no risk of commodity rate increase
4. Fewer systems exposed to elements = **longer lifespans**
5. System is controlled through **sophisticated monitoring devices** that are networked and provide real-time information
6. Building mechanical systems **costs the same** as a traditional systems
7. Up to **30% more efficient** than traditional boiler and chiller system
8. Up to **25% energy savings** in the summer cooling months


Business Pro Forma

- Pro Forma Developed to Show Project Payback
 - Pro Forma Included:
 - Assumptions
 - Financing
 - Energy Rates and Rate Increases for Gas and Electric
 - Wastewater Effluent Energy Value (MMBtu)
 - Cash Flow Analysis

CRES Financial Operations

- \$12 Million CRES Infrastructure financed with Qualified Energy Conservation Bonds (QECCBs)
- CRES Utility Rates Equivalent to Local Market Utility Rates
- CRES Revenue Pays QECCB Bonds and CRES Operational Expenses
- CRES Partners Share in Future Operational Savings

Preliminary Design



Preliminary Design

THERESA ST WWTP

- Use of Theresa St. WWTP Effluent
 - Current NPDES Permit Must be Met –
Temperature Limits
 - Project Avoided Second Permit by Discharging
Return Water to Same Location
 - WWTP Effluent Available Flow Rate
(Up to 28 MGD)

Preliminary Design


THERESA ST WWTP

- Lift Station at Theresa St. WWTP
 - WWTP Effluent Available Flow Rate
Up to 28 MGD to Supply the Heat Exchangers
 - Pump Design
 - Match Heat Exchangers Capacity
 - Phased Installation of Pumps (Modular by Design)
 - Pumps are Operated by VFD's
 - Spare Pump

Preliminary Design

THERESA ST WWTP

SYSTEM CURVE



Preliminary Design

THERESA ST WWTP

- Pumps Were Sized Based Upon System Curves
 - **Initial Build:** Three Pumps Total
(2 Pumps with 1 Spare)
 - **Peak Flow:** 16.5 MGD
 - **Average Flow:** Winter 9.9 MGD
 - **Average Flow:** Summer 6.5 MGD

Preliminary Design

THERESA ST WWTP

- Pumps Were Sized Based Upon System Curves
 - **Final Build:** Six Pumps Total
(5 Pumps with 1 Spare)
 - **Peak Flow:** 28 MGD
 - **Average Flow:** Winter 16.5 MGD
 - **Average Flow:** Summer 10.4 MGD

Preliminary Design

THERESA ST WWTP

- Pump Selection
 - Non Clog Submersible Pumps
 - All pumps are the same size
 - 110 Hp, 5,000 GPM @ 62.4 Ft Head
 - Flow and Head Vary with speed and number of pumps in use
 - VFD's to Control Flow Rate




Preliminary Design

THERESA ST WWTP

- Theresa St. WWTP
 - Lift Station and Piping Layout
 - 30-Inch Diameter Ductile Iron Pipe – 4,000 LF
 - Connection to UV Channel for Supply and Return




Preliminary Design



Preliminary Design


HEAT EXCHANGE FACILITY

Preliminary Layout




Preliminary Design

Summer



Winter




Preliminary Design

HEAT EXCHANGE FACILITY

- Sized Based Upon Effluent Flow and Temperature
- Sized and Phased Based Upon Projected Innovation Campus Building Loads
- All Phases Include a Redundant Heat Exchange Unit


CRES Plant Flow

Year 1 - July




— Effluent Available — Effluent Demand W/O Data Center — Effluent Demand With Data Center

CRES Plant Flow Year 1 - January




CRES Plant Flow


Year 12 - July



CRES Plant Flow Year 12 - January



Preliminary Design



Preliminary Design

- Distribution System
 - 36-inch Diameter HDPE Pipe
 - Twin Piping (Supply and Return)
 - Total of 6,100 LF

Preliminary Design


BUILDING SERVICE ENTRANCE

GENERAL NOTES

- UNLESS OTHERWISE NOTED, ALL EQUIPMENT, PIPING, VALVES, ETC. SHALL BE PROVIDED, INSTALLED AND MAINTAINED BY THE BUILDING TENANT.
- ONLY THE CRES SUPPLY / RETURN WATER SYSTEM IS SHOWN, PIPING LAYOUT AND DEVICES ON THE BUILDING SIDE OF THE HEAT EXCHANGER ARE NOT SHOWN. A MANUAL PRESSURE GAGE AND THERMOMETER ARE REQUIRED ON THE BUILDING SUPPLY AND RETURN LINES.

KEY NOTES

- HEAT EXCHANGER FLOW CONTROL VALVE PROVIDED AND CONTROLLED BY BUILDING CONTROL VENDOR.
- DUPLEX BASKET STRAINER WITH 1/16" SCREEN. TWO SINGLE STRAINERS MAY BE PROVIDED IN LIEU OF DUPLEX UNIT, PIPE BLOWDOWN PIPE TO NEAREST FLOOR DRAIN.
- FLOW METER PROVIDED BY UNL, INSTALLED BY CONTRACTOR. CONDUIT AND WIRE BACK TO METERING PANEL. CABLE GUTTER BY CONTRACTOR. SEE CRES BUILDING METER WIRING DETAIL. PROVIDE MINIMUM UPSTREAM AND DOWNSTREAM PIPE DIAMETERS AS SHOWN BETWEEN METER AND ANY VALVE / FITTINGS.
- PROVIDE A MINIMUM OF 15" SPACE BETWEEN METER LEG AND BYPASS LEG.
- PROVIDE PIPE SLEEVE AND LINK-SEAL WITH SS HARDWARE AT FLOOR PENETRATION. INSTALL SO THAT THREADED NUTS ARE EXPOSED.
- ALTERNATE WALL PENETRATION LOCATION IF SERVICE ENTRANCE IS LOCATED IN BASEMENT. PROVIDE SLEEVE AND SEAL PER NOTE 7.
- PRESSURE SENSOR PROVIDED BY UNL, INSTALLED BY CONTRACTOR. CONDUIT AND WIRE BACK TO METERING PANEL. CABLE GUTTER BY CONTRACTOR. SEE CRES BUILDING METER WIRING DETAIL.
- TEMPERATURE SENSOR PROVIDED BY UNL, INSTALLED BY CONTRACTOR. CONDUIT AND WIRE BACK TO METERING PANEL. CABLE GUTTER BY CONTRACTOR. SEE CRES BUILDING METER WIRING DETAIL.
- EXTRA THERMO-WELL FOR SENSOR CALIBRATION PROVIDED BY UNL, INSTALLED BY CONTRACTOR.
- PLATE AND FRAME HEAT EXCHANGER TO BE INSTALLED IN FIRST FLOOR OR BASEMENT OF TENANT BUILDING.
- 1" NORMALLY CLOSED BYPASS TO PREVENT ZERO FLOW CONDITIONS FOR EXTENDED OUTAGES.



CRES BUILDING SERVICE ENTRANCE PIPING SCHEMATIC

1
A1.01 SCALE: NO SCALE

CWS - CRES WATER SUPPLY
CWR - CRES WATER RETURN

Final Design

THERESA ST WWTP


- Lift Station Full Build-out = 5 pumps with a spare
- Prepackaged Pump Control Building
- Generator
- Pipe and Lift Station Within Levee Critical Zone

Final Design

THERESA ST WWTP


3. TEMPERATURE TRANSMITTER:
 PROVIDE TEMPERATURE TRANSMITTER WITH 100 OHM PT RTD SENSING ELEMENT FOR INSERTION IN OPEN CHANNEL FLOW. 0-150 DEGF. FURNISH RITZ/25 OR EQUAL. CONTRACTOR SHALL FABRICATE MOUNTING STRUCTURE SUITABLE TO IMMERGE TEMPERATURE ELEMENT IN FLOW STREAM SUCH THAT POTENTIAL ICE BUILD-UP DOES NOT AFFECT TEMPERATURE READING. TRANSMITTER SHALL BE INSTALLED IN PUMP CONTROL BUILDING. PROVIDE MANUFACTURER RECOMMENDED CABLE BETWEEN TEMPERATURE ELEMENT AND TRANSMITTER. PROVIDE 19R-#18 TWISTED/SHIELDED INSTRUMENT CABLE SHALL BETWEEN TRANSMITTER AND PRIMARY PUMP CONTROLLER. ALL CABLE SHALL BE IN CONDUIT.

INSTALL PRESSURE TRANSMITTER AND CONNECT TO PUMP CONTROL BUILDING PLC SEE NOTE 2, THIS SHEET





Final Design

THERESA ST WWTP




Final Design

THERESA ST WWTP




Final Design

THERESA ST WWTP



NORTH ELEVATION


SCALE: 3/8"=1'-0"



EAST ELEVATION


SCALE: 3/8"=1'-0"

PRODUCT COLORS	
STEEL ROOF	GRAY
BRICK	COLOR TO MATCH EXISTING BUILDINGS
LOUVERS	GRAY
DOORS	GRAY (ALUMINUM)
FASADA	
SGFFITS	GRAY
TRIM	



SOUTH ELEVATION

SCALE: 3/8"=1'-0"



WEST ELEVATION

SCALE: 3/8"=1'-0"



Final Design

THERESA ST WWTP


Corps Requirements

- Shoring
- Dewatering

- Emergency Plan for High Flows in Salt Creek
- Flowable Fill




SECTION 3
 SCALE: 1"=100' (C8)



SECTION 4
 SCALE: 1"=100' (C8)


Final Design

HEAT EXCHANGE FACILITY



Final Design

HEAT EXCHANGE FACILITY



Final Design


HEAT EXCHANGE FACILITY



SINCLAIR **hille**
architects

Final Design

HEAT EXCHANGE FACILITY






Final Design

CONTROLS


UNL INNOVATION CAMPUS - OVERVIEW



- LWWS LIFT STATION EFFLUENT
- CRES HEAT EXCHANGER PLAN
- NIC CAMPUS LOOP

Final Design


CONTROLS



- **LWWS LIFT STATION EFFLUENT**
3 Variable speed pumps.
Pump speed is automatically modulated to maintain a discharge pressure on HX primary side.

Final Design

CONTROLS



- **NIC CAMPUS LOOP**
3 Thermal Loop VFD Pumps
Automatically maintain differential pressure to campus.
- **CRES HEAT EXCHANGER PLANT**
3 Heat Exchangers
Automatically vary flow through heat exchangers to maintain thermal loop temperature to campus

Project Delivery and Construction

Project Schedule

- Phased
- Initial Coordination With Developer and City
- All agreements in place
- Complete design near Levee

Project Delivery and Construction

Project Schedule

- Selection of Construction Manager at Risk (CMAR)
- 30% CD's and GMP
- Funding by UNL
- NDEQ, USACE and NRD Review and Approval
- Beginning of Construction October 2013
- Final Completion August 2014

Project Delivery and Construction

THERESA ST. LIFT STATION AND PIPING



Project Delivery and Construction

THERESA ST. LIFT STATION AND PIPING



Project Delivery and Construction

THERESA ST. LIFT STATION AND PIPING



Project Delivery and Construction

HEAT EXCHANGE FACILITY



Project Delivery and Construction

HEAT EXCHANGE FACILITY



Project Delivery and Construction

HEAT EXCHANGE FACILITY



Project Delivery and Construction

HEAT EXCHANGE FACILITY



Project Delivery and Construction

HEAT EXCHANGE FACILITY



Project Delivery and Construction

HEAT EXCHANGE FACILITY



Project Delivery and Construction

DISTRIBUTION





NEBRASKA
INNOVATION
CAMPUS

© Nebraska Innovation Campus
230 Whittier Research Center
Lincoln, NE 68583-0859
Phone 402.472.5535 • Fax 402.472.9277

INNOVATE.UNL.EDU



@NIC_Innovates

Not just a place, a state of mind.